



ITB# 2023-09-02 Concrete Road Repair

The City of Huntington is seeking competitive bids from West Virginia licensed contractors for the removal and replacement of concrete roads totaling approximately 364 square yards of concrete across three (3) different roads/locations in Huntington WV. All federal and West Virginia state standards for concrete roads must be met with this project. West Virginia Department of Highway manuals can be found on their website.

City of Huntington reserves the right to reject any or all bids and waive any informalities in bidding. No bid may be withdrawn after the scheduled closing time for the receipt of bids for at least ninety (90) days. Bonding is required for this project.

A mandatory meeting will occur at Huntington City Hall, 800 5th Avenue on September 28th, 2023 at 9:00 am in City Council Chambers, room 121. Questions will be due no later than October 2nd, 2023 at 3pm and must be submitted through BidExpress. All bids will be due by October 4th, 2023 at 10am and must be submitted through the city's electronic bid site www.bidexpress.com. Any questions in regards to the use of Bid Express should be directed to Dan Underwood, Purchasing Director.

The locations that need repaired and have been marked on the street by the City of Huntington Public Works Department are located at the following:

- Elm Street in the Altizer neighborhood (approx. 140 square yards with a 10" depth – 11 segments) coordinates 38.414634, -82.373901 to 38.412390, -82.373538
- 6th Street West between 9th avenue and 11th avenue (approx. 133 square yards with an 8" depth – 7 segments) coordinates 38.408684, -82.463340 to 38.406772, -82.462586
- Sheppard Drive off of Maupin Road (approx. 91 square yards with an 8" depth – 7 segments) coordinates 38.412578, -82.395733 to 38.412150, -82.397118

Photographs of the road segments to be repaired are attached as a separate document within Bid Express.

SEGMENTS (sizes are approximate)

Elm Street

1. 30 feet x 20 feet x 10 inches
2. 18 feet x 8 feet x 10 inches
3. 45 feet x 18 feet x 10 inches
4. 10 feet x 10 feet x 10 inches
5. 15 feet x 15 feet x 10 inches
6. 30 feet x 15 feet x 10 inches
7. 30 feet x 20 feet x 10 inches
8. 22 feet x 20 feet x 10 inches
9. 22 feet x 20 feet x 10 inches



10. 28 feet x 15 feet x 10 inches
11. 15 feet x 15 feet x 10 inches

6th Street West

1. 12 feet x 30 feet x 8 inches
2. 44 feet x 20 feet x 8 inches
3. 40 feet x 20 feet x 8 inches
4. 86 feet x 20 feet x 8 inches
5. 86 feet x 10 feet x 8 inches
6. 22 feet x 10 feet x 8 inches
7. 48 feet x 10 feet x 8 inches

Sheppard Road

1. 15 feet x 35 feet x 8 inches
2. 10 feet x 15 feet x 8 inches
3. 10 feet x 15 feet x 8 inches
4. 60 feet x 25 feet x 8 inches
5. 15 feet x 62 feet x 8 inches
6. 15 feet x 15 feet x 8 inches
7. 10 feet x 10 feet x 8 inches

Requirements (include but not limited to)

Must meet WVDOH Standards and Specifications Roads and Bridges manual (2023 edition) & WVDOH Drawing Specs Manual

Removal of current concrete road segments – marked by Public Works

Haul away removed debris

Lay Down of new concrete roadway by vendor

Clean & Sweep

Mobilization

Traffic Control Devices