Huntington Stormwater Utility



Stormwater Management &

Sediment and Erosion Control Requirements for Construction Sites

Authorized by Huntington City Code Articles: 971, 970, 930, 935, 955,

Updated February 6, 2024

Stormwater Management Requirements

The Huntington Stormwater Utility is regulated by the WV Department of Environmental Protection for urban stormwater discharges and is required to implement runoff volume reduction strategies to manage stormwater onsite. Development and re-development sites of 5,000 square feet and greater must include stormwater control practices that reduce the *volume* of stormwater discharges.

The Utility's storm sewer system is aging and, in some places, under capacity to receive additional storm flows. One of the Utility's mission is to reduce or remove the stormwater flows that enter its system to reduce the street flooding that occurs.

Redevelopment: Development that will result in improvement by renewing, restoring, rebuilding, and/or new construction on, any developed property that encompasses 5,000 ft² or more, and that has one of the following characteristics:

- Land that currently has an existing structure, such as buildings or houses, or
- Land that is currently covered with an impervious surface, such as a parking lot or roof, or
- Land that is currently degraded and is covered with sand, gravel, stones, or other non-vegetative covering.

Redevelopment includes resurfacing pavements and projects that don't necessarily *create* or *reduce* square feet of impervious surfaces. A *reduction* of impervious surfaces in a development project that is 5,000 sq feet or greater requires stormwater management.

Stormwater management is required for all development of 5,000 ft² or more, *including* projects less than 5,000 ft² that are part of a larger common plan of development or sale.

Projects that are one acre or greater must provide proof of WVDEP approval under the WV Construction Stormwater Permit.

New development and redevelopment must manage the first one inch of rainfall on-site by utilizing the *runoff volume reduction* methodology and stormwater control practices. These include Bioretention cells, porous pavements, grassed swales, amended soils, and vegetated roofs. The runoff reduction stormwater practices that you choose should be able to manage the first one inch of rainfall on-site.

This includes the runoff from all impervious areas and managed turf. You can find the specifications for these practices in the guidance manual developed by the West Virginia Department of Environmental Protection. The "West Virginia Stormwater Management and Design Guidance Manual" is available on WVDEP's website. The link is here:

http://www.dep.wv.gov/WWE/Programs/stormwater/MS4/Pages/StormwaterManagementDesignandGuidanceManual.aspx

Some developments will meet incentive criteria and thus receive a reduction in the amount of stormwater that must be managed. A reduction may be applied if your site meets any of the following criteria listed below. The Utility reserves the right to require the full one-inch capture on-site if necessary, especially in areas that are prone to flooding.

A reduction of 0.2 inches from the one-inch runoff volume reduction standard may be applied to the following types of development:

a) Redevelopment

- b) Brownfield redevelopment
- c) High Density (>7 units per acre)
- d) Vertical density, (Floor to Area Ratio of 2 or > 18 units per acre)
- e) Mixed use and transit-oriented development (with ½ mile of transit)

Reductions may not exceed 0.75 inches. That means sites meeting four or more of the incentives will be required to manage on-site a minimum of .25 inches. It is at the discretion of the Utility to allow incentives.

Stormwater management is required for each contributing drainage area of the site. It is impermissible to oversize a stormwater structure on one portion of the site to compensate for a lack of controls on another portion of the site. This will only lead to the failure of that control structure.

The Utility requires that the drawings clearly depict the on-site stormwater management controls. A written narrative with calculations and a hydraulic analysis must also be submitted. The hydraulic analysis report shall include predevelopment and post-development calculations, any assumptions made for the calculations, methodology used, drainage area description, and a summary of the calculations. Calculations are to be performed for the following storm events and the design storm: 2-yr, 10-yr, 25-yr, 50-yr, and 100-yr. If you choose to use an infiltration stormwater design, the soil's infiltration rate must be included. Drawings and calculations must contain a Professional Engineer seal. For each stormwater control structure, include a detailed description of maintenance. Submit one PDF (electronic copy). The Utility cannot start the review until the electronic copy of the application package and the fee is received. We do not need a paper copy of the plans until the final revised plans are approved.

Based on the proposed stormwater controls, a maintenance agreement will be developed by the Utility. The agreement must be recorded at the County Courthouse. *A signed and recorded maintenance agreement must be submitted before approval*. The maintenance agreement will describe the inspection and maintenance activities and inspection frequency for the stormwater control practices. The maintenance agreement will contain remediation action in the event the structure requires maintenance or repair. The property owner or operator must provide verification of maintenance for the approved stormwater management practices. It is important that the hydraulic function of stormwater controls be maintained, and function as intended in perpetuity.

Please note: a contract engineer for the Huntington Stormwater Utility conducts engineering reviews. In accordance with Article 935.14 of the Huntington Stormwater Utility all costs and expenses for the review of the development project are to be borne by the owner(s) of the private facility. The Huntington Stormwater Utility will <u>not</u> commence review of the application until these expenses are paid. Cost data indicate that the engineering review costs are approximately \$1,600.00 per project. The fee for the erosion and sediment control permit is \$300.00.

Article 935.14 of the Huntington Stormwater Utility

(b) All costs and expenses of the Huntington Stormwater Utility incidental to the installation of private stormwater facilities, connection of a private facility to the Stormwater System, and installation of public facilities to facilitate and/or convey flows from a specific private facility to the Stormwater System, shall be borne by the owner(s) of the private facility. The amount of, and terms of payment for, these costs and expenses, shall be determined by the Huntington Stormwater Utility for such facility, in its sole discretion.

The Huntington Stormwater Utility looks forward to working with project managers and developers on their projects. If you have any questions regarding the stormwater requirements, please contact the Huntington Stormwater Utility at 304-781-1948 or 304-781-1952 or email: sherry.wilkins@huntingtonswu.com

Stormwater Management Checklist

This document contains the submission requirements and a checklist for the Huntington Stormwater Utility to review and approve the stormwater management controls on your site. There are <u>two</u> components to submit.

- 1. The Erosion and Sediment Control plan, and,
- 2. The Stormwater Management Plan

Stormwater management is required if you have a development project that will result in the disturbance of 5,000 square feet or greater, or the improvement or addition of 5,000 ft² of impervious surface, or a project that is less than 5,000 ft² but part of a larger common plan of development. Generally, both components are required, although some redevelopment sites may not need to obtain a sediment and erosion control permit. The two components may be submitted at the same time.

If your site is one acre or greater, the Stormwater Utility MUST receive a copy of the WVDEP approval. The approval is usually in the form of an email.

The required components must be submitted to the Huntington Stormwater Utility before construction begins. Please allow for thirty (30) days for review. Incomplete stormwater plans and narrative will result in delays in the review of your project.

Erosion and Sediment Control Plan

Your project will require a sediment and erosion control component.

A sediment and erosion control permit is required when a project disturbs 10,000 square feet or greater. For more details regarding Huntington's Erosion and Sediment controls go to page 13 of this document. These permits include the following:

For stand-alone projects such as demolition that do <u>not</u> include building a structure, *sediment and erosion controls are required on site*. A sediment and erosion control permit is required for projects 10,000 square feet or more.

- Application for Erosion and Sediment Control Permit.
- Applicable permit fees.
- Erosion and Sediment Control narrative and drawings. The checklist provides comprehensive details about what to include.
- Accompanying checklist.
- Plans shall be submitted as PDF files. Paper copies of plans are not required until the final revisions have been approved. Final revised plans must be folded to fit into an 8" x 11" folder. DO NOT SEND PLANS ROLLED IN A TUBE.

Stormwater Management Plan

The Huntington Stormwater Utility requires the runoff volume reduction method to *manage* and *reduce* stormwater discharges from the site. Please see the <u>West Virginia Stormwater Management and Design Guidance Manual</u> for specific controls. This manual can be found on WVDEP's MS4 website. For assistance in properly sizing stormwater controls, please use the West Virginia Stormwater Spreadsheet tool. Please contact the Huntington Stormwater Utility to obtain a copy of the spreadsheet (Excel). HSU will <u>not</u> provide engineering design for the applicant.

The checklist below is not an all-inclusive list of the details that should be included in the narrative and drawings. *To facilitate review of your project and to avoid delays the applicant must provide all the information in the checklist in the stormwater management plan*.

Narrative Report

- 1. A cover sheet that includes the owner, developer, and engineer's name, address, phone number, and email address.
- 2. Brief description of the project.
- 3. The narrative must include a statement of who will **be responsible** for the maintenance of the proposed stormwater management facilities.
- 4. The narrative must include a statement of who will **own** the stormwater management facilities in the event the property is sold after construction is completed.
- 5. Narrative that describes the stormwater controls that will be used.
- 6. Hydraulic analysis calculations.
- 7. Geotechnical report with results of soil testing.
 - a. Identify the Hydrologic Soil Group.
 - b. Identify the infiltration rate of the soil in inches per hour. **NOTE: if no infiltration test is conducted, then the soil infiltration rate must be assumed to be 0.07" per hour, and reflected in your calculations.
- 8. An explanation of how the <u>design engineer will verify</u> the stormwater controls were properly constructed. Note: These are not as-built drawings that observe structures after the fact. The construction process must be verified.
- 9. Printout of *spreadsheet that indicates the sizing of the stormwater controls.
- 10. For one acre and greater projects, include a copy of the WVDEP NOI approval.

Drawings

- 11. A cover sheet with the owner's name and contact information.
- 12. A drawing sheet that depicts the entire site's Stormwater Management Plan with the appropriate legend.
- 13. Each contributing drainage area on the site clearly marked and the appropriate stormwater BMP that is serving that drainage area. Elevations should be clearly marked. The stormwater from all contributing drainage areas is to be managed on-site with appropriate controls.
- 14. A drawing sheet that clearly delineates all **post-construction impervious surfaces**, including the total area of imperviousness in square feet.
- 15. Detailed construction notes. Including a plant list, components of soil media mixture, methods of disposal, etc.
- 16. A site plan that shows the property boundaries in relation to the City right of way.
- 17. Plan view and profile view of stormwater controls.
- 18. Description of materials used in stormwater controls, if applicable. (Such as; gravel, soils, geo-membranes, etc.)
- 19. Planting details,
 - a. Names of plants
 - b. Number of each plant type
 - c. Location of plants.
- 20. Location of storm sewers and catch basins.
- 21. A description of maintenance procedures for the stormwater facilities. (The maintenance agreement will be developed by the Utility based on the stormwater controls selected for the site)

- 22. All drawings, calculations, and narrative must be sealed by a WV Registered Professional Engineer.
- 23. As-built drawings are to be submitted within sixty days of completion of the stormwater controls. As-builts are to be submitted as PDF files and one hard copy.

A PDF file of the narrative and plans with (full size) drawings are to be provided (can be sent via email) to the Huntington Stormwater Utility. Paper copies are not required until the final revised plan is approved. At that time plans and drawings must be folded to fit into an 8"x11" folder. DO NOT SEND PLANS ROLLED IN A TUBE.

Erosion & Sediment Control Plans, Stormwater management plans, drawings, and calculations will be reviewed by Stormwater Utility staff and/or contract engineers. Once the stormwater plan has been deemed complete, **please allow thirty days for this review to take place**. Stormwater approval is valid for one year from issuance if the project does not begin immediately.

If you have any questions, please contact the Stormwater Utility office at 304-781-1948 or 304-781-1952.

If you wish to set up a preliminary plan review for your development, please contact the Business Services Advocate at 304-781-8348 to schedule a meeting.

*The spreadsheet is found on WVDEP's website and assists the designer in properly sizing the stormwater control structures. To obtain a copy of the spreadsheet please contact the Stormwater Utility.

Expenses and fees: Sediment and Erosion Control - \$300.00, Stormwater Management review expenses - \$1,600.00. Total: \$1,900.00

Please make checks payable to **Huntington Stormwater Utility**.

Please mail your check and application to the following address:

Huntington Stormwater Utility

P.O. Box 7578

Huntington, WV 25777

Attn: Director

This page intentionally left blank

Huntington Stormwater Utility

Application for Stormwater Management and Sediment & Erosion Control

Note: The application form and supporting documentation must be completed in its entirety, or it will be returned, and the project review may be delayed. The omission of required items may be cause for rejection or delay in the review of this submittal.

Applications, plans, drawings, and calculations must be emailed in PDF format to: sherry.wilkins@huntingtonswu.com. Permit and Expense Fees can be mailed to the Huntington Stormwater Utility, PO Box 7578, Huntington, WV 25777-1931, Attn: Director. Or, hand-delivered to our office located at 305 West 3rd Street, Huntington, WV 25701. Engineering reviews will start upon receipt of a complete application.

Property Owner Information			
Legal deed-holding property owner:			
Address of property owner:			
Phone Number:	Fax:		
Email:	Email:		
Project Contact			
Name:			
Address:			
Phone:	mail:		
Project	Information		
Project Name:			
Project Location:			
County Tax map number: Parcel ID Number:			
Latitude:	Longitude:		
Deed Book Number:	Deed Page Number:		
Existing Impervious Area (SQ FT):	Total footprint of project (SQ FT):		
Proposed Impervious Area (SQ FT): (Include driveways, sidewalks, rooftops, etc)			
Total earth disturbance of project (SQ FT)?			
If the project is one acre or greater of disturbance attach WVDEP Construction Stormwater Approval Letter.			
Did you perform a soil infiltration test? If not, assume an infiltration rate of .07" per hour. (See the WV Stormwater Management Design and Guidance Manual, Appendix B)			

	Runoff Reduction Credits (Select all that apply)
	Redevelopment
	Brownfield Redevelopment
	High Density (>7 units per acre
	Vertical Density (Floor to area ratio >2, or >18 units/acre
	Mixed use or transit-oriented development
	Total credits (0.2" each up to 0.75" max)
	Rainfall volume to manage (1" – total credits, Minimum 0.25")
property for the sediment and erd and articles (Articles (Artic	ed, hereby grant the designated officer of the Huntington Stormwater Utility the right to enter my purpose of pre-permit site visits, inspection, and monitoring for compliance with the approved osion control plan and stormwater management for this project. Ed, certify that I fully understand the provisions of the Huntington Stormwater Utility stormwater cles 970 & 971) and will construct and maintain all approved stormwater controls in accordance with ances and approved stormwater plans.
I understand tha	t a signed, notarized, and recorded stormwater facility maintenance agreement is required.
I understand tha facilities.	t the design engineer is required to be onsite during the construction of stormwater management
l will provide as-	built drawings within 60 days of completion of this project.
Property Owner	Signature ————————————————————————————————————

Print Name

Stormwater Management Checklist Items

All items shall be initialed by the owner or the design engineer as included or marked as N/A. If an item is marked as N/A, provide an explanation in the "Comments" Section below.

Narrative Description
Provide a brief description of the project, including the general scope, purpose, and proposed stormwater management facilities (SMFs) on the site. Narrative can be provided in the space below or included as an
attachment to this application.

Initial below	Existing Site Conditions	
	Existing and proposed contours, streets, and rights of way.	
	Existing utilities, sewers, and storm drainage structures and facilities.	
Proposed Site Plan		
	Location of proposed manholes, inlets, catch basins, and other stormwater infrastructure	
	Drawing that contains all post-construction impervious surface areas clearly marked, including the total in square feet. (i.e.: rooftop, driveway, sidewalks, parking, etc.)	
	Profiles of all proposed storm sewers, culverts, and stormwater facilities (including percent grade, pipe diameters, material, lengths, and invert elevations).	
	Locations, details, and standard drawings for all stormwater facilities. All stormwater facilities numbered for identification and reference.	
	Each contributing drainage area on the site clearly marked with an appropriate stormwater management facility serving that drainage area. Elevations clearly marked.	
	If stormwater management facilities require infiltration, provide a geotechnical report with soil testing results including hydrologic soil group and infiltration rate. If no testing was performed, soils are assumed to be type D with an infiltration rate of 0.07" per hour.	
	A planting plan (including names, quantities, and locations of all plants) appropriate for the chosen stormwater facilities (See Appendix F of the WV Stormwater Management and Design Guidance Manual).	
	All relevant dimensioning and notes needed for the proper construction of stormwater facilities are included on the drawings.	
	Any structural practices or facilities used that are not referenced in the WV Stormwater Mgmt and Design Guidance Manual are explained and illustrated with detailed drawings.	

Maintanana
Maintenance
Required maintenance activities for each stormwater facility provided on construction drawings. Indicate who will be responsible for each maintenance task. Maintenance activities are in accordance with the WV Stormwater Mgmt and Design Guidance Manual.
A completed contract between the property owner and an appropriate landscape company or equal for ongoing maintenance.
Design Calculation
Pre-development and post-development runoff calculations, including assumptions made, methodology used, drainage area description and summary of calculations for the 2, 10, 25, 50 and 100-year storm events.
Calculations showing storage volume needed to reduce post-development peak flows to pre-development levels.
Completed water quality spreadsheet with target water treatment volume.
Stormwater management facility sizing calculations showing storage equal to or greater than both the water quality target volume and the volume required to reduce post-development peak flows to predevelopment levels. Include a breakdown of storage for each layer of the stormwater facility, where applicable.
Additional Required Notes on Drawings
If stormwater facilities (such as bioretention cells) are to be used as sediment ponds during construction, include the following note on the contract drawings: "All sediment shall be removed from the basins and the bottom of each basin ripped to a depth of at least 18 inches prior to conversion to a stormwater management facility (Bioretention, infiltration or specific type of stormwater facility). Equipment shall not enter the basin to avoid compacting the subgrade and reducing infiltration capacity". The following note included on the contract drawings regarding stormwater facility installation: "Prior to installation of the stormwater management facilities, the contractor shall coordinate the installation
schedule with the design engineer. The design engineer must be given a minimum of one week notice prior to installation. The design engineer must be present during the installation of all layers. The design engineer must also provide a written report to the HSU certifying that the construction of the stormwater management facilities was done in accordance with the approved design."
Performance Bond and As-Built Construction Drawing Submittal
In some instances, a performance bond may be required. If one is required, the Utility will obtain prior to approval. The performance bond will be returned to the owner when the following items are received by HSU.
 Written report from the design engineer to the Huntington Stormwater Utility that the construction of the stormwater facilities was done in accordance with the approved design. As-built construction drawings for the stormwater facilities.
Comments

Please do <u>not</u> provide plans that are rolled up. Plans should be folded to fit into an 8" x 10" file folder.

Expenses and fees: Sediment and Erosion Control - \$300.00, Stormwater Management review expenses - \$1,600.00. Total: \$1,900.00

Checks are to be made payable to *Huntington Stormwater Utility*

Mailed to:

P.O. Box 7578
Huntington, WV 25777

Attn: Director

Huntington Stormwater Utility

Erosion & Sediment Control Plan Checklist

Project I	Name: Date:
Address:	
	Zip:
	cklist is provided to assist in the development of the erosion and sediment control plan to be submitted permit application.
<u>Section</u>	I – Sediment Control Plan Narrative
The narr	ative for the Sediment and Erosion Control Plan must include the following information:
1. Pro	ject Description
A.	Total project area.
B.	
C.	Total proposed area to be disturbed in square feet.
D.	Total volumes of proposed cuts/fill.
2. Exis	sting Site Conditions
A.	Description of the existing topography.
B.	Description of the existing vegetation.
C.	Description of the existing drainage.
3. Adj	acent Areas
A.	Description of adjacent areas which may be affected by site disturbance.
	1. Streams
	2. Lakes
	3. Wetlands
	4. Residential areas
	5. Roads
	6. Ditches, pipes, 7. Other
В.	Description of the downstream drainage path leading from the site to the receiving
b.	body of water (minimum distance of ¼ mile).
4. Crit	ical Areas
A.	Description of critical areas that are on or adjacent to the site.
В.	Description of special requirements for working in or near critical areas.

5.	30115		
	_ A.	Description	of critical on-site soils.
		1. 9	Soil name(s)
			Soil mapping unit
		3. I	
			Settleability
			Permeability
		6. I	Depth
		7.	Texture
		8. 9	Soil structure
6.	Frosi	on Problem A	Areas
٠.	A.		of potential erosion problems on site.
	_ ′ ''	Description	or potential crosion problems on site.
7.	Const	truction Stori	mwater Pollution Prevention Elements
	A.	Describe l	now each of the Construction Stormwater Pollution Prevention Elements has been
addre	_ ssed th	hrough the SC	
	В.	_	ne type and location of BMPs used to satisfy the required element.
	C.	Written ju	stification identifying why an element does not apply to the project.
	Requ	uired Element	s—Construction Stormwater Pollution Prevention Plan:
		1.	Mark clearing limits
		2.	Establish construction access
		3.	Install sediment controls
		4.	Stabilize soils
		5.	Protect slopes
		6.	Protect drain inlets
		7.	Convey stormwater in a non-erosive manner
		8.	Control other pollutants
		· · · · · · · · · · · · · · · · · · ·	Control dewatering
		10.	Maintain BMPs
		11.	Manage the project
		12.	Stabilization
		13.	Establishing Grass
8.	Const	truction Phas	
	_ A.	Construction	·
	_ B.	Construction	phasing (if proposed)
9.	Const	truction Sche	dule
-•	Α.		oposed construction schedule.
	_ /·· В.	•	Construction Activities
			Proposed wet season construction activities.
		'	The state of the s

2. Proposed wet season construction restraints for environmentally sensitive/critical areas.
10. Engineering Calculations
A. Provide Design Calculations.
1. Sediment ponds/traps
2. Diversions
3. Waterways
4. Run/off/stormwater calculations
If halfy enjoyees matter carealations
Section II – Erosion and Sediment Control Plan
The Erosion and Sediment Control Plans for your project must contain the following information:
1. General
A. Vicinity Map
B. Address, Parcel No., and Street Names labels
C. Erosion and Sediment Control Notes
2. Site PlanA. Legal description of subject property.
A. Legal description of subject property B. North Arrow.
C. Indicate boundaries of existing vegetation, e.g. tree lines, pasture areas, etc.
D. Identify and label areas of potential erosion problems.
E. Identify any on-site or adjacent critical areas and associated buffers.
F. Identify FEMA base flood boundaries.
G. Show existing and proposed contours.
H. Indicate drainage basins and direction of flow for individual drainage areas.
I. Label final grade contours and identify developed condition drainage basins.
J. Delineate areas that are to be cleared and graded.
K. Show all cut and fill slopes indicating the top and bottom.
3. Conveyance systems
A. Designate locations for swales, interceptor trenches, or ditches.
B. Show all temporary and permanent drainage pipes, ditches, or cut-off trenches required for
erosion and sediment control.
C. Provide minimum slope and cover for all temporary pipes or call-out pipe inverts.
D. Show grades, dimensions, and direction of flow in all ditches, swales, culverts, and pipes.
E. Provide details for bypassing offsite runoff around disturbed areas.
F. Indicate the location and outlets of any dewatering systems.
4. Location of Champungton Management Churchung
4. Location of Stormwater Management StructuresA. Identify the location of any stormwater management structures.

5.	Erosion and Sediment Control Measures		
	_ A.	Show the locations of sediment traps(s), pond(s), pipes, and structure(s).	
	_ B.	Dimension pond berms widths and inside and outside pond slopes.	
	_ C.	Indicate the trap/pond storage required and the depth, length, and width dimensions.	
		Provide typical section views through pond and outlet structure.	
		Provide typical details of gravel cone, standpipe, and/or other filtering devices.	
		Detail stabilization techniques for outlet/inlet.	
		Detail control/restrictor device location and details.	
		Specify mulch and/or recommended cover of berms and slopes.	
		Provide rock specifications and detail for rock check dam(s), if applicable.	
		Specify spacing for rock check dams as required.	
	_ K.	Provide front and side sections of typical rock check dams.	
		Indicate the locations and provide details and specifications for silt fabric.	
	_ M.	Locate the construction entrance and provide details.	
6	Doto	iled Drawings	
0.			
	_ A.	Any structural practices used that are not referenced in the Manual should be explained and illustrated with detailed drawings.	
		mustrated with detailed drawings.	
7	Othe	r Pollutant BMPs	
, •	A.	Indicate on the site plan the location of BMPs to be used for the control of pollutants other than	
	_ ^.	sediments, e.g., concrete was water.	
		scamency e.g., consider was water.	
8.	Moni	itoring	
- •	Α.	Describe inspection reporting responsibility, documentation, and filing.	